

Demolition & Construction


Noise Control for Occupied NICUs

Jack B. Evans, PE

JEAcoustics
Evans(at)JEAcoustics

Reduction of Noise Disturbances in the NICU
During Facility Modification and Expansion

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 1/30


Engineered Vibration Acoustics & Noise Solutions

- **Jack B. Evans, PE**
President & Principal Engineer
- **Education & Experience:**
 - 25+ Years Acoustical Consultation
 - 6 Years Facilities Engineering
 - BS Architectural Engineering, Univ. of Texas '75
- **Case Study of Phoenix Children's Hospital**
 - NICU Expansion & Rearrangement Planning
- **Measurements at Memorial Hermann Woodlands Hospital**
 - Data Acquired for Evidence Based Design Study
- **Practical Measures to Isolate Occupied NICUs from Demolition & Construction Noise**

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 2/30

Agenda

- Acoustics, Noise & Vibration Terminology
- Transmission Paths
 - Airborne, Duct borne, Structure borne
- Acoustical & Vibration Criteria for NICUs
- Common Noise & Vibration Sources
 - Continuous Interior, Transient Interior
 - Intrusive Exterior (Environmental)
- Demolition & Construction (Unique)
 - Airborne, Impact, Impulse, Explosive

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 3/30

Overview

- Protect Newborns, Mothers & Staff from:
 - Sleep interruption
 - Stress & Startle
 - Communication Interruption
 - Loss of Monitor & Alarm Signals
- Building Acoustics & Noise Control works for Normal Occupancy
- Special and Temporary Measures may be used for Demolition and Construction Noise

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 4/30

Vocabulary / Glossary of Terms

◦ Attenuation	◦ Noise Reduction Coefficient (NRC)
◦ Bandwidth	◦ Octave (freq. ratio 2)
◦ Continuous	◦ Performance / Prescriptive
◦ Damping	◦ Q (directionality)
◦ Decibel (dB)	◦ Reflective / Reverberant
◦ Equivalent Level (Leq)	◦ Sound Transmission Class (STC)
◦ Frequency	◦ Spectrum
◦ Gravity	◦ Transient (Intermittent, Random)
◦ Hertz (cps)	◦ UL Assembly
◦ Isolation	◦ Vibration
◦ Just Detectable Difference	◦ Weighting (A, C, Linear/Flat)
◦ Kilo, KHz	◦ X
◦ Level (Lp, Lv),	◦ Y
◦ Masking	◦ Z

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 5/30

1. Acoustics vs. Sound Isolation

- **Absorber (Rating = NRC):**
 - Low Density, Porous: Insulation, Foam, etc.
- **Barrier (Rating = STC):**
 - Dense, Solid: Wood, Glass, GWB, Concrete
- **Damper:**
 - Mass or Visco-elastic Material Applied
- **Diffuser:**
 - Articulated Reflective Surface
- **Flanking Path:**
 - "Leak," "By-Pass" or Secondary Path
- **Demonstration**

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 6/30

2a. Airborne vs. Structure Borne

- Propagation Within a Room:
 - Direct Source to Receiver Path or Reflection
- Room to Room Airborne Transmission:
 - Horizontal via Wall, Door, Duct or Penetration
 - Vertical via Floor-Ceiling Assembly, Shaft or Penetration
- Room to Room Structure Borne Transmission:
 - Horizontal via Partition, Floor Slab, Pipes or Ducts
 - Vertical via Bldg. Columns, Pipe and Duct Risers
- Outside to Inside Airborne Transmission:
 - Horizontal via Windows, Doors, Wall or Openings
 - Vertical via Roof, Roof-top Equip. Ducts, Skylights

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 7/30

2b. Airborne-Structure Borne Interaction

- Airborne Sound-Induced Structure Borne Vibration:
 - Loud Low-Frequency Sound Causes Vibration in Lightweight Structures, Such as Ceilings and Partitions
- Radiated Airborne Sound from Structure Borne Vibration:
 - Vibrating Surface Area Acts Like Loudspeaker to Radiate Sound
- Sound Reinforcement from Re-radiated Structure Borne:
 - Radiated sound is Additive Second Source
- Structure Borne Path Can Bypass "Buffer Zones":
 - Vibration Travels Long Distance with Little Attenuation
 - Sound is Easily Dissipated

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 8/30

3a. NICU Acoustical Criteria


- Facility Criteria vs. Operational Criteria
(This presentation focuses on Facility Criteria)
- NICU Standards Criteria
 - Operational: Occupant Generated Noise
 - Facility: Building Systems Noise
- Building Design (Facility) Criteria
 - Continuous Background Noise (NC/RC)
 - Sound Isolation/Privacy (STC/IIC)
 - Room Acoustics/Reverberation (T60/NRC)
 - Green Guide for Health Care (Future LEED)






2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 9/30

3b. Building Design (Facility) Criteria








Partition & Floor-Ceiling Assy. Continuous Background Noise

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 10/30

3c. Measurements vs. Criteria


- Data from an Evidence-Based Design Study by WHR Architects, Inc. & JEAcoustics






- Corridor Noise Measurements
- Private Patient Room Measurements
- NICU Measurements

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 11/30

Woodlands Hospital* LDR & NICU







Floor Plans: "Pod" Style LDR and Small NICU

* Plans by WHR Architects, Inc.

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 12/30



- ### 4. Common Noise & Vibration Sources
- Continuous
 - Bldg. Equipment
 - AHU, Exhaust
 - Pumps, Pipes
 - Elec. Transformers
 - Cont. On Equip.
 - Light Ballasts
 - Traffic Noise (Intrusive Environmental)
 - Transient
 - Speech
 - Rolling
 - Impacts
 - Footfall Traffic
 - On/Off Equip.
 - Elevators
 - Patient Monitors
 - Pagers
 - Environmental
 - Street Traffic
 - Helicopter & Aircraft
 - Sirens
 - Outdoor Bldg. Equip.
 - Amplified Music
 - Outdoor Machines
- 2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 15/30

- ### 5. Demolition & Construction Noise & Vibration Sources
- Machinery
 - Compressors
 - Generators
 - Vent Fans
 - Lamp Ballast
 - Vacuum
 - Pallet Jack
 - Power Lift
 - Tools
 - Hammers
 - Saws
 - Circular
 - Reciprocating
 - Drills
 - Anchor Setters
 - Grinders
 - Chippers
 - Miscellaneous
 - Speech
 - Material Staging
 - Impacts
 - Scraping
 - Radios
 - Backup Alarms
- 2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 16/30


6. Source - Path - Receiver

- Reduce Noise, Vibration Where Created
 - Attenuate
 - Isolate
- Prevent or Reduce Energy Along Path
 - Isolate
 - Damp
- Attenuate Noise at Receiver
 - Attenuate
 - Mask


2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 17/30

- ### 7. Implementation
- Space Planning
 - Phasing & Scheduling
 - Involve the Construction Contractor
 - Pre-Determine For Various Conditions
 - Temporary vs. Permanent Noise Barriers
 - Off-site vs. On-site fabrication of assemblies
 - Methods of Demolition
 - Materials Staging & Movement
 - Materials & Methods of Construction
 - Feasibility of Temp. NICU Evacuation/Relocation
- 2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 18/30


8. Demolition & Construction Expansion Plan* & Measurements



9. Small and Large NICU Stat. (Ln) Noise Measurement Results




10a. Simulated Demolition Noise & Vibration Measurement Sources



10b. Simulated Demolition Noise & Vibration Measurement Locations



11. Simulated Demolition Impact & Vibration Measurement Results



12c. Demolition & Construction Noise Control Recommendations

- Hospital should meet with the architect/engineer and construction team
 - Not adequate to instruct contractor to use quiet construction methods
 - Predetermine and agree to specific impact and machine-tool noise measures
 - Create buffer areas for NICU admin & infant areas
 - Non-sensitive spaces adjacent to partition re-radiation surfaces
 - No doors or windows that directly connect NICU with Construction Zone
 - Retrofit door seals on frames + 2nd solid-core door in frame if connecting door
 - Retrofit 2nd layer of laminated glass in window frames
 - Choose non-impact demolition procedures.
 - Choose non-vibratory demolition procedures
 - Schedule noisy procedures during most busy time in NICU
 - Intrusive transient events not as perceptible during busy time with local transients
 - Place slab isolation joints in new concrete work
 - Discontinuities should be complete
 - Place resilient floor mats on demo, fabrication and construction floors
- 2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 24/30

12. Demolition & Construction Noise Control Plan Illustration

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 25/30

12a. Demolition & Construction Noise Control Recommendations

Architectural

- 1. Temporary sound barrier at partitions
 - a. Blanket w/ barrier septum
 - b. Mass-loaded vinyl sheet
 - c. Drywall on furring studs
- 2. Modify Floor:
 - a. Rubber floor surface
 - b. Floor deck over resilient underlayment
- 3. Vibration isolate isolette legs, counters
- 4. Door seals
- 5. Modify NICU ceilings:
 - a. Ceiling hanger vibration isolators
 - b. Substitute composite barrier-absorber tiles
 - c. Lay barrier sheet or blanket over ceiling

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 26/30

12b. Demolition & Construction Noise Control Recommendations

Structural (major cost & complexity)

- Isolate the NICU slab from demo
 - o Cut the slab along a column line
 - o Support the slab edge along the cut line.
 - Secondary Columns and beams
 - Isolator pads between corbel support and beam.
- Insert "whole building" vibration isolators
 - o Vertical vibration transmission from above or below
 - o Check ducts, pipes, etc.

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 27/30

12c. Demolition & Construction Noise Control Recommendations

Building Systems Engineering (MEP)

- Segregate Demo/Const from NICU
 - o Reroute Ducts between NICU and Construction Zone
 - o Place Attenuators in R/A Transfers & Ducts
 - o Lagging Enclosures Around Ducts & Pipes.
 - o Flexible Couplings in Pipes, Ducts & Conduits
- Vibration Isolation For Pipes
- Seal Wall Penetrations

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 28/30

Summary

- Sensitive spaces temporary relocation
- Scheduling of demolition and construction sequences.
 - o Individual impact noise events may be tolerated,
 - o Continuous or repetitive events may sensitize occupants
- Multiple simultaneous impact events are additive
 - o Slightly louder
 - o More feelable
- Physical control of noise and vibration at source
- Re-radiated sound from partition and ceiling surfaces
- Floor vibration transmission into furnishings and casework
- Novel conceptual ideas

2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 29/30

Acknowledgements

- Moe Stein, FAIA, HKS / SCG Architects, Phoenix, AZ (Formerly The Stein-Cox Group, Inc.)
- Phoenix Children's Hospital, Phoenix, AZ
- Mark Vaughan, AIA, WHR Architects, Houston, TX
- Woodlands Memorial-Hermann Hospital
- Kathleen Philbin, PhD, re: J. Perinatology papers 2000 & 2006

Help Finding an Acoustical Consultant
National Council of Acoustical Consultants
(www.NCAC.com)

*Oh, By the way:
The contractor doesn't really finish,
At least not in the time allocated.*


2/5/07 JEAcoustics / Engineered Vibration Acoustics & Noise Solutions 30/30

Demolition & Construction

Noise Control for Occupied NICUs

Thanks for your kind attention.

Any Questions?

 **JEAACOUSTICS**
Engineered Vibration Acoustic & Noise Solutions

Jack B. Evans, PE

Evans(at)JEAcoustics

2/5/07 JEAoustics / Engineered Vibration Acoustics & Noise Solutions 31/30